GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Dated 17th January 1912.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer to Government up to 29th January 1912, inclusive, for constructing quarters for the Assistant Chief Line Inspector and Telephone Clerk at Kankanhalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1912.

2. The plans, detailed estimate and conditions may be seen at the Chief Electrical Engineer's office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for the Assistant Chief Line Inspector and Telephone Clerk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chief Electrical Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	Per	Main building	Out houses	Telephone Maistry's quarters
		Quantity	Quantity	Quantity
Earthwork, excavating foundation and filling basement	C. yd.	55	23	15
Chunam concrete foundation	C. ft.	583	312	161
Coursed rubble in lime mortar, foundation and basement	,,	1,357	351	410
Superstructure, burnt brick in mortar	,,	2,662	1,296	836
Do flat arch work	,,	97	31	31
Stone slabs for stable gate with two 3" round holes (7'×1½'×½')	Each	...	2	...
Burnt brick in mortar pillars 1½ foot sqr., 6½' high with base and capital complete.	,,	5	...	...
Plastering with mortar	Sqr.	43·49	22·52	15·91
Pointing with mortar	,,	2·96	0·89	1·24
Stone slabs, roughly dressed exposed surface	C. ft.	9	1	9
White and color washing	Sqr.	46·45	23·41	17·15
Flooring with 1½" Cuddapah slabs over a bed of 6" sand with cement pointing, etc.	,,	8·29	1·66	2·54
Gravel flooring	C. yd.	...	3	...
First class Mangalore tile roofing over teak reepers 2"×1", half tiles, borders, etc., complete.	Sqr.	15·82	6·38	6·27
Ridge tiles set in mortar and cement pointing	R. ft.	35	34	24
Cornice (9"×6")	,,	23	...	...
Honne wood work with oiling	C. ft.	100·12	25·53	26·99
Teakwood doors battened 1¼"	S. ft.	126	...	...
Teakwood windows panelled shutters outside and glazed inside with iron bars.	,,	72	...	...
Teakwood rectangular ventilators glazed	,,	42	...	...
Teak ornamental eave boarding 10"×¾" with painting	R. ft.	134	...	...
Teak ornamental barge-boarding 12"×¾" with painting	,,	49	...	...
Teak weather boarding 1" thick at ends of verandah	S. ft.	32	...	...
Cement pointing to roofs of rear rooms and verandah	Sqr.	7·39	...	...
Honne wood door, battened, 1¼"	S. ft.	...	36	18
Honne wood windows 1¼" with iron bars	,,	...	12	15
Honne wood rectangular ventilators glazed	,,	...	...	6
Silicate painting 3 coats	Sqr.	5·10	0·96	0·72
Teakwood turned finials at gable ends	Each	2	...	2
Fencing round the building with gay wire and 2" pipe	L. S.	...	...	...
Add for probable extra works in foundation and basement of main quarters.	,,	...	...	...
Clearing site and removing debris and forming drains	,,	...	...	...
Burnt stone pillars for verandah (9'×12"×6") cutting notches, etc., complete.	Each	...	...	5
Ornamental eave-boarding in honne wood 9"×¾" with painting	S. ft.	...	...	49
Barge-boarding (12"×¾")	,,	...	...	52

S. D. IYENGAR,
For *Chief Electrical Engineer.*